

Specifications

Page 6 of 7 Pages

15	PHASE 3 - SANITARY SEWER		
A	Sewer Testing	2174	L.F.
B	Sewer Cleanup	2174	L.F.
C	Sewer Manhole	13	Each
D	8" PVC Sewer Main	2174	L.F.
E	6" Sewer Laterals	773	L.F.
F	6" Sewer Cleanouts	61	Each
	TOTAL PHASE 3 - SANITARY SEWER		\$ 133,746.00
16	PHASE 3 - WATER DISTRIBUTION		
A	Water Testing	3509	L.F.
B	Water Cleanup	3509	L.F.
C	4" C-900 Water Main	1679	L.F.
D	8" C-900 Water Main	1830	L.F.
E	3/4" Water Services (no meter)	61	Each
F	Fire Hydrants	9	Each
	TOTAL PHASE 3 - WATER DISTRIBUTION		\$ 146,640.00
	TOTAL PHASE 3		\$ 1,208,487.00
17	PHASE 4 - SITEWORK		
A	Construction Entrance	3	Each
B	Silt Fence	2500	L.F.
C	Excelsior Matting - Swales	2080	S.Y.
D	Strip Topsoil (1' depth)	12434	C.Y.
E	Furnish & Place Imported Borrow	31728	C.Y.
F	Curb & Gutter	2600	L.F.
G	Stone Stabilization	2200	Tons
H	Base Paving - Type B	571	Tons
I	Top Paving - Type C	429	Tons
J	Replace Topsoil - On site (6" depth)	4875	C.Y.
K	Seed & Mulch	25344	S.Y.
L	Inlet Protection	7	Each
M	Rip Rap	14	Tons
	TOTAL PHASE 4-SITEWORK AND SEDIMENT & EROSION CONTROL		\$ 593,147.00

This page becomes part of and in conformance with proposal for:

Bunting and Murray Construction Corporation

Submitted by: Jcm Date: 3/21/08

Signature _____
Date of Acceptance _____